

**HTES Ref:** B17643

**Date:** 08 Apr 2015

**Cadtech**

**Tel:**

**Fax:**

**For the attention of: Mike**

Dear Sirs/Madam

**Ref: Posi-Strut Beam**

**Job Ref :- Collection from HTES Bury St Edmunds Howarth House Hollow Road Bury St Edmunds Suffolk**

We thank you for your enquiry and have pleasure in submitting our Quotation for the supply of Posi-Strut Beam on the aforementioned development.

General notes:

**Terms of Payment:**

**Delivery:**

To a mutually agreeable programme is free to the nearest vehicular point of access and is based on full loads. (No crane off load allowed) (Normally 7-15 working days from receipt of order and approval of final design) Please note the responsibility for the unloading process lies with the contractor.

**Crane:**

Should a crane be deemed necessary we cannot and will not be held responsible for any hire charges. Whilst we endeavour to deliver on an agreed day, we cannot be held responsible for a particular time of day.

**Fixed Price:**

Prices are nett and held firm for deliveries up to and including

Please see pricing information attached.

We trust this quotation is of interest to you. If you require any further information please do not hesitate to contact us.

Yours faithfully

**Steve Meacham**

**Howarth Timber Engineered Solutions Ltd.**

smeacham@howarth-timber.co.uk



Howarth Timber Engineered Solutions Ltd.  
Howarth House  
Hollow Road  
Bury St Edmunds  
Suffolk  
IP32 7QW  
Tel: 01284 772700  
Fax: 0844 801 2321

# Posi- Joist - Detailed Schedule



Customer: **Cadtech**  
 Job Ref : **Collection from HTES Bury St Edmunds Howarth House Hollow Road Bury St Edmunds Suffolk**  
 HTE Ref: **B17643A**  
 Date: **08/04/2015**

House Type : Terrace House

Floor Dead Load (kN/m2)-0.685




Floor Live Load (kN/m2)-0.750

UNTREATED  
Spacing-600

<u>Ref</u>	<u>Qty.</u>	<u>Description</u>	<u>Span</u>	<u>Depth</u>	<u>Cost Per Posi</u>	<u>Total</u>
------------	-------------	--------------------	-------------	--------------	----------------------	--------------

**Main Area**

## Floor Trusses

B01	1		2.387 mm	178 MM	£26.37	£26.37
<b>2 Units Securely Fastened in Factory</b>						
F01	14		4.300 mm	225 MM	£27.86	£390.04
F01G	1		4.300 mm	225 MM	£80.47	£80.47
<b>2 Units Securely Fastened in Factory</b>						
F02	4		3.450 mm	225 MM	£22.86	£91.44
F02G	1		4.300 mm	225 MM	£67.66	£67.66
<b>2 Units Securely Fastened in Factory</b>						

## Ancillary Items

3	No	47x97 R/W TR26 3600mm	
6	No	22x100 Sawn 4800mm	Temporary Bracing
8	No	35x72 R/W TR26 4800mm	Noggins
150	No	ZS35N Z Clip 35mm	
6	No	Heavy Engineered Restraint Straps HES15B10	
2	No	IUB215/100 - Face Fix PosiJoist Hanger 215mmx100mm	SDS Screw Fixing
2	No	SDW 22258	

**Total for Set Main Area:**

  
**£788.40**

## Decking & Glue

### Ancillary Items

33	No	Egger Peel Clean Extra TG4 22x600x2400
5	No	Egger D4 Adhesive

**Total for Set Decking & Glue:**

**£357.68**



# Posi- Joist - Detailed Schedule



Customer: **Cadtech**  
 Job Ref : **Collection from HTES Bury St Edmunds Howarth House Hollow Road Bury St Edmunds Suffolk**  
 HTE Ref: **B17643B**  
 Date: **08/04/2015**

House Type : Holiday Home

Floor Dead Load (kN/m2)-0.685

Floor Live Load (kN/m2)-0.750


UNTREATED

Spacing-600

<u>Ref</u>	<u>Qty.</u>	<u>Description</u>	<u>Span</u>	<u>Depth</u>	<u>Cost Per Posi</u>	<u>Total</u>
------------	-------------	--------------------	-------------	--------------	----------------------	--------------

**Main Area**

## Floor Trusses

R01	21		8.650 mm	253 MM	£84.72	£1779.12
-----	----	---	----------	--------	--------	----------

## Ancillary Items

### Ancillary Items

4	No	47x97 R/W TR26 3600mm				
6	No	22x100 Sawn 4800mm		Temporary Bracing		
6	No	35x72 R/W TR26 4800mm		Noggins		
120	No	ZS35N Z Clip 35mm				

**Total for Set Main Area: £1,884.34**

**Grand Total EXCLUDING VAT £1,884.34**